BRUHAT BANGALORE MAHANAGARA PALIKE

BBMP/2020-21/OW/WORK_INDENT42418

APPROVED SCHEDULE - B

No.EE/BTP/BBMP/E-PMT/02/2020-21, Date: 28.05.2020

Name of Work:Improvements to Solid Waste Management in Ward No.8

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of Mallikarjuna Swamy G.R	
				In Figures	In Words
1	8	Supplying ,installation ,Commissioning and Testing CP PLUS 3 MP 50 meters ip bullet camera,1/3" 3MP PS CMOS Image Sensor,Max 25fps@3MP, 25/30fps@1080P,H.264, H.264H, H.264B , MJPEG dual-codec encoding,DWDR, Day/Night(ICR), 3DNR, ROI, AWB, AGC, BLC, HLC,3.6mm fixed lens (6mm optional),IR Range of 50 Mtrs, IP67, SD Card, PoE,Mobile Software: iCMOB, gCMOB,CMS Software: KVMS Pro, vOptimus Pro inclusive of all taxes and transportation charges as per the direction of Engineer in Charge	No	19385.0	Rupees Nineteen Thousand Three Hundred Eighty Five Only
2	1	Supplying ,installation ,Commissioning and Testing CP PLUS 32 Ch. H.265 4K Network Video Recorder Up to 32 channel IP camera input H.265/H.264 dual codec decoding Up to 8Mp resolution preview and playback Max 200Mbps incoming bandwidth Support 4 SATA HDDs up to 24TB, 2 USB(1 USB3.0) HDMI / VGA simultaneous video output Support Multi-brand network cameras ONVIF Version 2.4 conformance Mobile Software: iCMOB, gCMOB inclusive of all taxes and transportation charges as per the direction of Engineer in Charge	No	55988.0	Rupees Fifty Five Thousand Nine Hundred Eighty Eight Only
3	1	Providing and Supplying NAS hard disk drives 6 TB inclusive of all taxes and transportation charges as per the direction of Engineer in Charge	No	19125.0	Rupees Nineteen Thousand One Hundred Twenty Five Only
4	1	Supplying ,installation ,Commissioning and Testing D-Link 24-Port Gigabit Switch With 4 Combo SFP Ports inclusive of all taxes and transportation charges as per the direction of Engineer in Charge	No	29546.0	Rupees Twenty Nine Thousand Five Hundred Forty Six Only
5	2	Supplying ,installation ,Commissioning and Testing D-Link 8-Port Gigabit Switch With 2 Combo SFP Ports inclusive of all taxes and transportation charges as per the direction of Engineer in Charge	No	23855.0	Rupees Twenty Three Thousand Eight Hundred Fifty Five Only
6	1	Providing and Supplying CAT6 OUT Door 305 mtr Cable Box inclusive of all taxes and transportation charges as per the direction of Engineer in Charge	No	53777.0	Rupees Fifty Three Thousand Seven Hundred Seventy Seven Only
7	1	Providing and Fixing Media converter Giga Dlink inclusive of all taxes and transportation charges as per the direction of Engineer in Charge	No	10211.0	Rupees Ten Thousand Two Hundred Eleven Only
8	665	Providing and Fixing OFC cable single mode 6 core inclusive of all taxes and transportation charges as per the direction of Engineer in Charge	Mt	138.3	Rupees One Hundred Thirty Eight and Thirty Paise Only
9	2	Providing Cctv MS poles with camera fixing brackets, 5 to 6 mtr height Box inclusive of all taxes and transportation charges as per the direction of Engineer in Charge	No	18832.0	Rupees Eighteen Thousand Eight Hundred Thirty Two Only
10	2	Providing and Fixing MS Boxes for Poles with rust proof powder coating Box inclusive of all taxes and transportation charges as per the direction of Engineer in Charge	No	7952.0	Rupees Seven Thousand Nine Hundred Fifty Two Only
11	2	Providing and Fixing Electrical work for boxes for power supply, fixing PVC Boards with three pin socktes and switches with protection MCB and cabling to street light electrical poles as per the direction of Engineer in Charge	No	7115.0	Rupees Seven Thousand One Hundred Fifteen Only
12	2	Providing Internet charges connecting CCTV with IP Based for one month	No	2929.0	Rupees Two Thousand Nine Hundred Twenty Nine Only
13	2	Providing and Fixing SFP-LX-SM GIGA MODULE Box inclusive of all taxes and transportation charges as per the direction of Engineer in Charge	No	5440.0	Rupees Five Thousand Four Hundred Forty Only

Signature of the contractor

Executive Engineer

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Ra... Mallikarjuna Swamy G....	
				In Figures	In W...ds
14	5	Providing and Fixing Fibre Optic PATCH Chords Box inclusive of all taxes and transportation charges as per the direction of Engineer in Charge	No	1814.4	Rupees One Thousand Eight Hundred Fourteen and Forty Paise Only
15	2	Erecting of pole .The pole shall be erected n cement concrete work(1:2:4) including earthwork excavation and refilling of planting depth of the pole to the ground level and the copping CC shall be upto 0.6m above ground level as per IS 2713-7.1 Erection of lightduty pole on footpath a) 7.5m as per IS 410 Sp 5 charges as per the direction of Engineer in Charge	No	5356.0	Rupees Five Thousand Three Hundred Fifty Six Only
16	2	Providing and Fixing HDMI Cables 10 Mtrs inclusive of all taxes and transportation charges as per the direction of Engineer in Charge	No	5440.0	Rupees Five Thousand Four Hundred Forty Only
17	1	Supplying ,installation ,Commissioning and Testing Video Manager Application Software for Display and Management of Camera on Video Display Box inclusive of all taxes and transportation charges as per the direction of Engineer in Charge	No	27203.0	Rupees Twenty Seven Thousand Two Hundred Three Only
18	15	Supplying ,installation ,Commissioning and Testing Patch cords CAT6 2 Mtr Box inclusive of all taxes and transportation charges as per the direction of Engineer in Charge	No	1005.0	Rupees One Thousand Five Only

Signature of the Contractor

Executive Engineer
Byarayanapura Division
BBMP, Bangalore - 92

3/08

03/08